

RECEIVED

DEC 19 2000

DEPT OF ECOLOGY

**COMPREHENSIVE STORMWATER MANAGEMENT PLAN**

**FOR AGENCY REVIEW**

**SEATTLE-TACOMA INTERNATIONAL AIRPORT  
MASTER PLAN UPDATE IMPROVEMENTS**


Prepared for

**PORT OF SEATTLE**  
Seattle-Tacoma International Airport  
P.O. Box 69727  
Seattle, Washington 98168-0727

Prepared by

**PARAMETRIX, INC.**  
5808 Lake Washington Blvd. N.E., Suite 200  
Kirkland, Washington 98033-7350

December 2000  
556-2912-001 (28)



AR 019463

## TABLE OF CONTENTS

	<u>Page</u>
EXECUTIVE SUMMARY	ix
1. INTRODUCTION .....	1-1
1.1 PURPOSE .....	1-1
1.2 GOALS AND OBJECTIVES .....	1-2
1.3 DOCUMENT ORGANIZATION .....	1-2
2. STORMWATER MANAGEMENT STANDARDS .....	2-1
2.1 WATER QUANTITY MANAGEMENT STANDARDS .....	2-1
2.1.1 Definition of Level 1 and Level 2 Flow Control Standards .....	2-1
2.1.2 Base Year .....	2-2
2.1.3 Target Watershed Flow Regime .....	2-3
2.1.4 Updated Detention Requirements .....	2-4
2.2 WATER QUALITY MANAGEMENT STANDARDS .....	2-5
2.2.1 Regulatory Requirements .....	2-5
2.2.2 Water Quality Treatment Requirements for New, Redeveloped, and Retrofitted Surfaces .....	2-6
3. DESIGN CONSIDERATIONS AND HYDROLOGIC ANALYSIS METHODOLOGY	3-1
3.1 AIRPORT-SPECIFIC DESIGN GUIDELINES .....	3-1
3.1.1 Overall Guidelines .....	3-1
3.1.2 Wildlife Proximity to Open Detention Ponds .....	3-1
3.1.3 Proximity to Aircraft Movement Areas .....	3-4
3.1.4 Feasibility of Creating Artificial Aquifer Storage in New Embankments ..	3-5
3.2 DAM SAFETY .....	3-7
3.3 HYDROLOGIC ANALYSIS METHODOLOGY .....	3-8
4. EXISTING CONDITIONS .....	4-1
4.1 DRAINAGE BASINS .....	4-1
4.2 CONVEYANCE SYSTEMS .....	4-5
4.2.1 Storm Drainage System .....	4-5
4.2.2 Industrial Wastewater System .....	4-7
4.2.3 Pump Facilities .....	4-9
4.2.4 Recent SDS to IWS Reroutes .....	4-10
4.3 STORMWATER DETENTION .....	4-10
4.4 HYDROLOGIC MODELING/WATER QUANTITY .....	4-12
4.4.1 Model Development .....	4-12
4.4.2 Long-term Simulation .....	4-13
4.4.3 Flow Duration Analysis of Target Watershed Flow Regime .....	4-13
4.5 EXISTING BMPs AND WATER QUALITY .....	4-13
4.5.1 Best Management Practices .....	4-13
4.5.2 SDS Water Quality .....	4-17
4.5.3 IWS Treatment Performance .....	4-19
5. PROPOSED MPU IMPROVEMENTS .....	5-1
5.1 SUMMARY OF PROPOSED IMPROVEMENTS .....	5-1
5.2 LAND USE CHANGES .....	5-1
5.2.1 Future Land Use .....	5-4
5.2.2 Changes in Impervious Area .....	5-4

**TABLE OF CONTENTS (continued)**

	<u>Page</u>
6.	<b>HYDROLOGIC MODELING OF FUTURE CONDITIONS AND STORMWATER QUANTITY MANAGEMENT</b> ..... 6-1
6.1	<b>HYDROLOGIC MODELING</b> ..... 6-1
6.1.1	Model Development..... 6-1
6.1.2	Detention Options ..... 6-1
6.1.3	Estimated Detention Storage..... 6-3
6.1.4	Water Quality of Stormwater Stored in Vaults..... 6-3
6.2	<b>STORMWATER QUANTITY MANAGEMENT</b> ..... 6-3
6.2.1	Low Stream Flow Impacts and Mitigation ..... 6-3
6.2.2	Retrofit of Stormwater Detention for Existing Airport Areas..... 6-10
6.3	<b>CONSTRUCTION SCHEDULE</b> ..... 6-11
6.4	<b>OTHER KING COUNTY MANUAL REQUIREMENTS</b> ..... 6-12
6.4.1	Flood Analysis..... 6-12
6.4.2	Downstream Analysis Impacts ..... 6-12
6.4.3	Conveyance System ..... 6-12
6.4.4	Restricting Public Access to Ponds with Steep Slopes..... 6-12
7.	<b>FUTURE STORMWATER QUALITY</b> ..... 7-1
7.1	<b>STORMWATER DRAINAGE SYSTEM WATER QUALITY TREATMENT BMPS</b> ..... 7-1
7.1.1	Treatment BMPs for New Development ..... 7-3
7.1.2	Treatment BMPs for Redevelopment Projects ..... 7-6
7.1.3	Existing Areas in Compliance with Treatment Requirements ..... 7-8
7.1.4	Treatment BMP Retrofitting ..... 7-9
7.1.5	Areas Not Practicable for Retrofitting ..... 7-10
7.2	<b>SUMMARY OF BMP COVERAGE</b> ..... 7-12
7.3	<b>NON-POLLUTION-GENERATING IMPERVIOUS SURFACES</b> ..... 7-14
7.4	<b>ROOF TOPS</b> ..... 7-14
7.5	<b>IWS AKART DETERMINATION</b> ..... 7-15
7.6	<b>PERVIOUS SURFACES</b> ..... 7-15
7.6.1	Managed Areas..... 7-15
7.6.2	Unmanaged Areas ..... 7-16
7.7	<b>OTHER ACTIONS BENEFITING WATER QUALITY</b> ..... 7-16
7.7.1	Removal of PGIS from Subbasins ..... 7-18
7.7.2	Elimination of Existing Pollutant Sources in Areas to be Redeveloped ... 7-18
7.7.3	Source Controls ..... 7-19
7.7.4	Pollutant Removal in Lake Reba ..... 7-19
7.7.5	Low Streamflow Augmentation in Des Moines Creek ..... 7-21
7.7.6	Construction Erosion Control ..... 7-21
7.7.7	Snowmelt Facilities ..... 7-22
7.7.8	Enhancement of Wetland Water Quality Functions ..... 7-22
7.7.9	Miller Creek Buffer Enhancement..... 7-22
7.7.10	Miller Creek Stream Channel Restoration and Enhancement..... 7-22
7.7.11	Level 2 Hydrologic Controls..... 7-23
7.8	<b>STORMWATER FACILITY MAINTENANCE</b> ..... 7-23
8.	<b>REFERENCES</b> ..... 8-1

**APPENDICES (Under Separate Cover)**

**VOLUME 2**

- A HYDROLOGIC EVALUATION OF STORMWATER DRAINAGE BASIN CHANGES AND DETENTION POND PERFORMANCE BETWEEN 1994 AND MASTER PLAN COMPLETION

**VOLUME 3**

- B HSPF MODEL CALIBRATION REPORT

**VOLUME 4**

- C EXISTING DETENTION FACILITY DATA  
D PROPOSED DETENTION FACILITY FIGURES  
E BMP SIZING ESTIMATIONS PER UNIT PGIS AREA  
F FEASIBILITY OF STORMWATER INFILTRATION REPORT  
G WATER RIGHTS ON MILLER CREEK  
H WATER QUALITY TREATMENT FACILITY SIZING CALCULATIONS FOR SASA, STEP, AND THIRD RUNWAY  
I LANDSCAPE MANAGEMENT PLAN  
J MILLER CREEK FLOODPLAIN ANALYSIS SUMMARY  
K EMBANKMENT AQUIFER CONSTRUCTION MEMO  
L GEOTECHNICAL ENGINEERING REPORT FOR THE THIRD RUNWAY EMBANKMENT CONSTRUCTION  
M WATER QUALITY BMP COST ESTIMATES FOR AREAS DETERMINED TO BE NON-PRACTICABLE FOR RETROFITTING  
N INDUSTRIAL WASTEWATER SYSTEM MONTHLY DISCHARGE MONITORING REPORTS (JANUARY 1999 – OCTOBER 2000)  
O IWS OUTFALL HYDRAULIC CAPACITY MODELING RESULTS  
P DES MOINES CREEK AND MILLER CREEK DOWNSTREAM ANALYSES  
Q PROPOSED STORMWATER CONVEYANCE FIGURES  
R CONSTRUCTION EROSION CONTROL  
S HDR EVALUATION OF STORM CONVEYANCE SYSTEM  
T PHYSICAL PROPERTIES OF PROPOSED ROOFING MEMBRANES AND PRELIMINARY ROOF SURVEY FIGURES  
U RUNWAY/TAXIWAY GRASS INFIELD LANDSCAPE MANAGEMENT PLAN  
V SEATTLE TACOMA INTERNATIONAL AIRPORT SPILL PREVENTION CONTROL AND COUNTERMEASURES PLAN  
W ENERGY DISSIPATION DESIGN CRITERIA AND PARAMETERS  
X SUPPLEMENTAL NEPL SOIL INFORMATION  
Y STORMWATER ANALYSIS OF THE ASR SITE  
Z IWS LAGOON STORAGE CAPACITY MODELING

## LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
3-1 Aircraft Movement Area Restrictions on Detention Pond Siting.....	3-6
4-1 Miller Creek and Des Moines Creek Watersheds (Existing Conditions).....	4-2
4-2 Future STIA Drainage Subbasins and 1994 Land Use.....	4-3
4-3 STIA and Surrounding Development 1994.....	4-6
4-4 Water Quality Treatment for Existing Surfaces.....	4-16
5-1 Proposed Master Plan Projects... ..	5-2
5-2 STIA Drainage Subbasins and 2006 Land Use.....	5-3
5-3 STIA Subbasin Future Impervious Areas.....	5-5
6-1 Proposed Detention Facilities for Master Plan Projects.....	6-4
7-1 Water Quality Treatment for New and Retrofitted Surfaces.....	7-2

## LIST OF TABLES

<u>Table</u>	<u>Page</u>
3-1 Summary of water impoundment behind earthen dams.....	3-7a
4-1 Summary of Miller, Walker, and Des Moines Creek drainage areas at STIA and change in impervious area between 1994 baseline and 2006 future conditions. ....	4-4
4-2 IWS configuration (land use, storage, treatment rate, discharge rate, number of overflows).....	4-8
4-3 IWS pump stations. ....	4-9
4-4 SDS to IWS reroute projects implemented during 1994-1998.....	4-10
4-5 Existing stormwater detention facilities.....	4-11
4-6 BMP inventory for existing STIA subbasins as they will be configured for Master Plan Update build-out.....	4-14
4-7 Estimated BMP size per acre of PGIS. ....	4-15
4-8 Seattle-Tacoma International Airport runoff quality (1994-2000) compared to regional and national urban stormwater quality studies. ....	4-17
6-1 Existing detention ponds serving Seattle-Tacoma International Airport with potential for expansion. ....	6-2
6-2 Summary of required detention facility volumes. ....	6-5
7-1 Water Quality BMP design parameters, Third Runway and connecting taxiways.....	7-3
7-2 Water quality BMP design parameters, SASA.....	7-4
7-3 Water quality BMP design parameters, NEPL.....	7-5
7-4 Water quality BMP design parameters, South 154 <sup>th</sup> Street.....	7-6
7-5 Water quality BMP design parameters, North Cargo Area.....	7-6
7-6 Water quality BMP design parameters, STEP.....	7-7
7-7 Summary of existing areas in compliance with water quality treatment BMP requirements. ....	7-9
7-8 Summary of water quality treatment BMP coverage for STIA SDS subbasins. ....	7-13

**LIST OF TABLES (continued)**

<u>Table</u>		<u>Page</u>
7-9	Summary of Master Plan Update improvements related to water quality mitigation activities and benefits. ....	7-17
7-10	Seattle-Tacoma International Airport source control BMPs. ....	7-19